

# Raised Access Floor Module Innovation


Offsite fabrication of building services has been utilized across the construction industry for several decades. As Building Information Modelling (BIM) has grown in maturity and wide spread use, buildings have become more complex and space allocation for building services has been pushed to the limits to drive down overall building volume. This increased efficiency has created significant challenges in construction and several benefits. The challenges include the complexity of the design and construction to accommodate building services in a reduced space. The benefits include the reduction in costs due to fewer materials being required and the subsequent environmental impact of reduced materials. Reduced energy costs driven by a smaller volume building without compromising the buildings functional requirements. To provide the benefits and address the significant design and construction challenge, Skanska has implemented an innovative approach to the building services off site fabrication.

The AstraZeneca New Cambridge Site project has extraordinarily high aspirations for architectural statement, interior finishes as well as high performance from the building services with a BREEAM Excellent target. To provide an integrated approach to achieve the architectural needs, building services performance and optimization of the building volume, the project has extended the building services module construction approach to include the raised access floor area of the building. The raised access floor covers 12,800 square metres of the project. The pedestals for the raised accessed floor have been fabricated off site with the supports engineered to be utilized as the primary building services supports. This has allowed for an increase in overall space efficiency to meet the building requirements. Additional benefits of this approach include:


Efficiency of deliveries to site. The modules were stacked 6-10 per lorry and 390 modules will be delivered to site in approximately 55 lorry loads. This is in contrast the hundreds of lorry deliveries that would have been required across 10 subcontractors who have scope on the modules.

The work in the fabrication shop was done at benchtop height, in a clean well ventilated assembly area with simple logistics providing significant improvement of the work environment for the operatives to complete their work.


The shift of this traditional site work to the factory environment has resulted in an estimated 120,000 operative hours being removed from the project site. This reduction in site labour translates to fewer operatives working on site and a reduction of the overall impact to the site logistics, local neighbours and local traffic.



# Raised access floor BIM model



## Raised access floor BIM model with fan coil unit and branch ductwork






## Level 1 Modules in Installed on Site



## Section through raised access showing services passing through the module to 3 elevations



### Roof:

- Sprinkler
- Blind Control
- Lighting
- Vesda System
- Emergency Lighting
- PA System
- Fire Alarm
- Wifi

### Level 2:

- Power
- Data
- HVAC Supply
- HVAC Extract
- Heating & Hot Water
- Chilled Water
- Leak Detection
- IBMS
- Emergency Lighting
- Fan Coils
- Fire Alarm
- Sprinkler
- PA System
- Wifi
- Fire Alarm

### Level 1:

- Wifi
- Sprinkler
- Lighting
- Emergency Lighting
- PA System
- Daylight Sensor
- Occupancy Sensor
- Exit Signage
- Fire Alarm



# Assembly and Fabrication Shop



# Unistrut Frame Assembly and Bracketry





## Work at Benchttop Height and Duct Work Installed




# Module to Module Alignment





## Piping Installed Ready for Insulation





## 6 Modules ready for delivery

